BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20593

SCHEDULE-B

NAME OF WORK: Construction of RCC drain in 4th and 5th cross road north side at Prashantha nagara in ward no.13, Shetty halli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor J C RAMACHANDRA		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clodscomplete as per specfication & as per direction of Engineer-in-charge	Cum	307.76	75.0	Rupees Seventy Five Only	23082.00
2	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curingcomplete as per specfication & as per direction of Engineer-in-charge	Cum	64.94	4658.0	Rupees Four Thousand Six Hundred Fifty Eight Only	302490.52
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing,complete as per specfication & as per direction of Engineer-in-charge	Cum	189.17	5513.0	Rupees Five Thousand Five Hundred Thirteen Only	1042894.21

Signature of the Contractor

Executive Engineer

4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specfication & as per direction of Engineer-in-charge	Qtl	113.5	6413.0	Rupees Six Thousand Four Hundred Thirteen Only	727875.50
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification	Sqm	931.4	272.0	Rupees Two Hundred Seventy Two Only	253340.80
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per specfication & as per direction of Engineer-in-charge	Sqm	49.68	1450.0	Rupees One Thousand Four Hundred Fifty Only	72036.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction complete as per specfication & as per direction of Engineer-in-charge	Cum	307.76	75.0	Rupees Seventy Five Only	23082.00
					Total	2444801.03
					Percentage	-8.53%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer